

SECTION 011100 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 SCOPE OF WORK PERFORMED UNDER THIS CONTRACT

Work under this contract shall consist of complete replacement of pump/motor assemblies, pump guide rails, new variable frequency drives and control panels, replacement of all wet well interior piping, corrosion resistant coating of all interior wet well surfaces, new flow meter, and electrical service upgrades at each pump station; new emergency generator and transfer switch at each pump station; refurbishment of hoist structures and rail assemblies; new SCADA improvements; new above ground piping/valve/air release valve assembly for Pump Station No. 3; plug valve and check valve replacements at Pump Station No. 2; and with all related work specified and shown on the Drawings.

1.2 ENUMERATION OF DRAWINGS & SPECIFICATIONS

Following are the Drawings and Specifications which form the Contract Documents as set forth in Section 1.1 of the General Conditions:

Drawings

See Cover Sheet of the Contract Plan Set

Specifications

See Table of Contents in Contract Documents

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 011100